

**TENDER NOTICE**

1	Name of The Work	Tender for soil filing at BAL BATIKA, DAV Public School Cantt. Raod Khagaul, Patna.
2	Estimated Area	Soil Filing- 67053 CFT
3	Time of Completion	25/03/2026
4	Date of Tender Notification	21/02/2026
5	Last Date/Time for Receipt of Bids	28/02/2026
6	Name and Address of office Inviting Tender	DAV Public School, Cantt. Road, Khagaul, Patna (Bihar)
7	Contact Number of Procurement Office	DAV Public School, Cantt. Road, Khagaul, Patna (Bihar) <a href="http://www.davkhagaul.org">www.davkhagaul.org</a> , E-mail:- <a href="mailto:davkhagaul@hotmail.com">davkhagaul@hotmail.com</a>
8	Help Numbers	Schools Telephone Number-9798353206

**Following points need attention**

1. The school shall not be liable to pay any tax, freight, etc. which has not been expressly stipulated in the quotation in the event of acceptance of the quotation. The school will deduct TDS as per rule of Income Tax.
2. On acceptance of the quotation, it will become a contract and the contractor shall be bound by the terms and conditions of the quotation as well contractor must full fill the terms and conditions of Government of India / Bihar.
3. The quantity of articles indicated in the attached statements not be increased or decreased without permission of undersigned.
4. The description of the above said works details can be had from the office of the Principal, DAV Public School, Cantt. Road, Khagaul, Patna. The payment will be made to the contractor through A/C payee cheque after the finishing of the work and duly approved by the architect.
5. Quotations which do not comply with the above conditions are liable to be rejected.
6. Earth filling shall be carried out in layers not exceeding 200–300 mm thickness, and each layer shall be properly watered and compacted using mechanical means to achieve the required density.
7. The filling material shall consist of good-quality earth for top layers.
8. Filling work up to a maximum height of 3'-0" shall be carried out strictly as per the approved levels, drawings, and site requirements.
9. Adequate field compaction tests, as and when required, shall be conducted to ensure proper compaction and stability of the filled earth.

Principal  
DAV Public, school,  
Khagaul, Patna

Manager  
DAV Public, school,  
Khagaul, Patna

**TENDER NOTICE**

1	Name of The Work	Tender for soil filing and Fixing the Pavers Blocks at DAV Public School Cantt. Raod Khagaul, Patna.
2	Estimated Area	Soil Filing- 178900 CFT 80 MM thick M35 grade CC Pavers Blocks- 57013 Sft
3	Time of Completion	31/03/2026
4	Date of Tender Notification	21/02/2026
5	Last Date/Time for Receipt of Bids	28/02/2026
6	Name and Address of office Inviting Tender	DAV Public School, Cantt. Road, Khagaul, Patna (Bihar)
7	Contact Number of Procurement Office	DAV Public School, Cantt. Road, Khagaul, Patna (Bihar) <a href="http://www.davkhagaul.org">www.davkhagaul.org</a> , E-mail:- <a href="mailto:davkhagaul@hotmail.com">davkhagaul@hotmail.com</a>
8	Help Numbers	Schools Telephone Number-9798353206

**Following points need attention**

1. The school shall not be liable to pay any tax, freight, etc. which has not been expressly stipulated in the quotation in the event of acceptance of the quotation. The school will deduct TDS as per rule of Income Tax.
2. On acceptance of the quotation, it will become a contract and the contractor shall be bound by the terms and conditions of the quotation as well contractor must full fill the terms and conditions of Government of India / Bihar.
3. The quantity of articles indicated in the attached statements not be increased or decreased without permission of undersigned.
4. The description of the above said works details can be had from the office of the Principal, DAV Public School, Cantt. Road, Khagaul, Patna. The payment will be made to the contractor through A/C payee cheque after the finishing of the work and duly approved by the architect.
5. Quotations which do not comply with the above conditions are liable to be rejected.
6. Paver blocks must be 80mm thick, M- 35-40 grade, machine-pressed and vibration compacted, Conforming to IS: 15658. Bedding layer to be 25-30mm coarse sand, well leveled and compacted. Earth filling to be executed in proper layers with adequate compaction to achieve levels and slope.
7. The requirement of brick batts PCC over the filled up soil may also be assessed.

Principal  
DAV Public school,  
Khagaul, Patna

Manager  
DAV Public, school,  
Khagaul, Patna